BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT44682

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/06/2020-21, Date: 03-09-2020

Name of Work:Improvements to Roads and Drains Thindlu colony Kempegowdanagara and Surrounding areas in ward No 9 Vidyaranyapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B M Muniraju	
				In Figures	In Words
1	494.22	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	256.05	Rupees Two Hundred Fifty Six and Five Paise Only
2	793.8	Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work.	Sqm	116.85	Rupees One Hundred Sixteen and Eighty Five Paise Only
3	119.07	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	779.03	Rupees Seven Hundred Seventy Nine and Three Paise Only
4	321.78	Providing and laying Plain cement concrete of mix 1:3:6 with with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days etc complete as per specifications and directions of engineer in charge of the work.	cum	5692.45	Rupees Five Thousand Six Hundred Ninety Two and Forty Five Paise Only
5	6.48	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	cum	6102.0	Rupees Six Thousand One Hundred Two Only
6	10.8	Providing ruled pointing 20 mm deep to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	158.03	Rupees One Hundred Fifty Eight and Three Paise Only
7	1891.2	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	1028.31	Rupees One Thousand Twenty Eight and Thirty One Paise Only
8	198.24	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	cum	5879.42	Rupees Five Thousand Eight Hundred Seventy Nine and Forty Two Paise Only
9	1598.4	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge - Data rate	Sqm	2453.62	Rupees Two Thousand Four Hundred Fifty Three and Sixty Two Paise Only
10	12.96	Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - (Data rate Approved).	Sqm	5688.36	Rupees Five Thousand Six Hundred Eighty Eight and Thirty Six Paise Only

B.M. Muniraju

Signature of the Contractor

01/12

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

1/12